

SECTION 16:
INSPECTIONS, TESTS, AND SYSTEM CERTIFICATION FOR
STANDPIPE SYSTEMS

- 16.1 **Flow Tests.** Standpipe systems shall be required to pass a flow test that complies with the most current NFPA 14 and NFPA 25 editions.
- 16.1.1 **Procedure.** Standpipe systems shall require a flow test. The AHJ shall approve the test method. The installer shall provide all the test equipment needed. The installer shall test the integrity and certify the minimum flow of the system before final acceptance by the AHJ.
- 16.1.2 **Documentation.** At the final acceptance test, the contractor shall provide the AHJ with a copy of the Test Certificate. This document is required before the AHJ signs any forms approving the system.
- 16.2 **Tests and Inspections.** Certified system contractors shall perform tests and inspections for standpipe systems. The test and inspection shall comply with the most current edition of applicable NFPA standards. The contractor shall submit the test and inspection report electronically to the AHJ within 30 days of completion of the test.